



PROCUREMENT OF A SERVICE PROVIDER FOR THE MECHANICAL CLEANING OF DRANAGE BASIN BETWEEN RAILWAY BRIDGE AND MOSHONGO NEW LOW COST HOUSING (NANCEFIELD EXTENSION 4)

1.1 Scope of Work:

- 1.1.1 Clear and grab (0-300mm) vegetation and light bushes
- 1.1.2 Load and dispose municipal dumping site

1.2 Extent of area

- 1.2.1 The area affected is 4 000m²
- 1.2.2 It is between the toe of the railway track and the lower houses along the drainage channel
- 1.2.3 Clear and grab to be on both sides of the existing lined drainage channel

1.3 Existing Conditions

- 1.3.1 Continuous sewer flow in the exiting stormwater drainage channel
- 1.3.2 There bulk sewer pipes mostly on the surface as well as water reticulation in the area
- 1.3.3 Transnet railway infrastructure
- 1.3.4 Partial lined stormwater drainage channel
- 1.3.5 Wetland
- 1.3.6 Aqua animals
- 1.3.7 Vegetation (very light to medium)
- 1.3.8 Unstable soft grounds
- 1.3.9 Informal peasants
- 1.3.10 Inaccessible established paths

1.4 Conditions for work execution

- 1.4.1 No work will be allowed without the Vhembe District Municipality representative on site
- 1.4.2 Existing sewer and water reticulation to be properly identified prior the commencement of the clear and grab operations to avoid damage
- 1.4.3 Transnet toe earthworks not to be disturbed during the clear and grab operation
- 1.4.4 Existing municipal drainage channel not to be damaged

1.5 Plant Requirements

- Medium tracked excavator (mandatory)
- Hauling trucks (mandatory)
- A loader (recommended optional)

PRICING or OFFER:

R_____ for 4 000m² all incl. (taking into consideration plant establishment, works execution and de-establish the plant)

CONTRACTOR'S PRODUCTION CAPABILITY

_____ Day(s)

